

SQUARE SCRUB[®] Versatility²



EBG-Series Floor Preparation Machines



Doodle
mop
BY SQUARE SCRUB
EBG - 16



Powerful Mopping Made EASY!

- Improves soil and biofilm removal.
- Designed for everyday floor mopping.
- 4000 rpm motion drastically improves cleaning vs hand mopping.
- Works with 16" & 18" disposable microfiber mopheads.
- Disposable microfiber pads help reduce cross contamination.
- Great for cleaning luxury vinyl tile & other textured flooring.
- Doodle Mop weighs 12lbs with a 30' power cord.
- Includes Carry Strap & Handle Trigger.
- Easy to clean & maintain.

For more info visit
mop.squarescrub.com



Disposable Microfiber Pads



SS 0410Z
25 pads per pack

*Not intended for heavy recovery cleaning, or for use with the tile and grout pad.



Before

After



How clean are your floors?

Your floors are most likely one of the main sources of cross-contamination of pathogens.

More than 1.7 Million Hospital Acquired Infections (HAI) occurred in hospitals in the United States in 2002, resulting in 99,000 Deaths.

- Average Hospital Acquired Infection cost per patient is \$23,735.
- Total cost of \$40.3 billion representing 11% of total hospital spend in 2009.



According to the CDC

1 IN 30 U.S. patients will contract at least 1 Hospital Acquired Infection during the course of their hospital stay. The need to improve infection control, and improve cleaning practices is at an all time high.

Square Scrub set out to improve the traditional way of cleaning with Disposable Microfiber Mops.



While traditional microfiber mop handles work, they do not compare to the **superior cleaning power** of the Square Scrub Doodle Mop.

Not all floors are created equal. Traditional mop heads struggle getting into hard to reach textures and crevasses. The Doodle Mop by Square Scrub allows you to superbly clean all flooring types. No machine on the market today has the superior soil removal like the Square Scrub Doodle Mop.

Using the Square Scrub Doodle Mop along with the disposable microfiber pad provides the most effective cleaning tool available on the market today. Square Scrub technology will help **drastically reduce the chances of cross-contamination**, reduce Hospital Acquired Infections, and allow for superior soil removal.



Before

After

** Patent Pending

***Specifications & information contained in this catalog are subject to changes without notice.




EBG-20/C

SQUARE SCRUB

Versatility²

PIVOT




EBG-28

INNOVATION

evolved

New pivoting head
for balanced
contact & easier
control.



Redesigned sleek
7 gauge stainless
steel base.

Smooth Pivoting Action

The new pivoting head releases the control handle from the bottom of the base, allowing the machine to pivot freely front to back.



This pivoting motion follows uneven floors more efficiently.




Near perfect weight distribution

The new floating design allows the head to have near perfect front to back and side to side weight distribution.

Near perfect weight distribution allows the entire pad to make equal contact with the floor, allowing equal distribution of the work across the entire pad.

Other designs place more pressure on the front or rear of the machine causing uneven pad wear.



squarescrub.com
800-557-6822





**Patent Pending

***Specifications & information contained in this catalog are subject to changes without notice.

Improved Isolators

The new completely redesigned Pivot style machines include an all new 2 ¼" long isolator. This is 50% longer than the previous isolator, which should result in longer part life. The longer isolator reduces stretching, which can lead to wear and tear.




Vibration Reducing Isolators

The new Pivot design includes 10 low profile isolators mounted on the pivoting base. These isolators have been tuned and balanced to remove nearly all felt vibration by the operator.

Redesigned Dust Skirt



The new dust skirt now wraps all the way around, and overlaps in the back for better dust containment and removal.



**Patent Pending

New Trigger Assembly

The new trigger is much more robust and sensitive at the same time. It is now locked in place with steel guide pins riding in nylon bushings for smooth action. The handle is now a full solid welded steel assembly.



Two-Piece Handle

The new optional two-piece handle uses two additional knobs to release the operator handle and cord from the base. Taking this weight off makes the machine lighter and easier to load for transporting.

squarescrub.com
800-557-6822

**Patent Pending

***Specifications & information contained in this catalog are subject to changes without notice.

Adjustable Handle


Now that the operator handle no longer impacts the weight of the head on the floor, it can be adjusted with freedom.

Older non-floating designs are very sensitive to the position and weight of the handle, requiring the full upright position to be kept at all times.



Quick Release Cord Wrap

With just a quick twist, the new cord wrap unwinds the entire cord and gets the machine to work faster.



Optional Features

Hour Meter
(Standard on EBG-28)



Manual Power Switch



Extra Weights
(Only available on EBG-20/C)



New Silver Grip Face



9" SS 051103V



16" SS 051603V



20" SS 142003V




28" SS 142803V


The grip face allows any tool to adhere even better to the machine by significantly reducing slippage. Reducing slippage between the pad and grip face causes less friction between the pad and the plate. This allows more power transfer to the work surface, and reduces pad wear. Many of our products adhere directly to the grip face without the need for drivers. The Square Scrub grip face covers the entire plate in a single sheet and is more chemically resistant. Most competitors use multiple strips, which can leave the bearing system vulnerable to chemical contaminants.

Grip Face Comparison

Grip Face Teeth Per Square Inch



Grip Face Teeth Height



Tan Grip Face Teeth Height - .10"

New Silver Grip Face Teeth Height - .10"


Black Grip Face Teeth Height - .07"

White Grip Face Teeth Height - .028"

New Bearing Seal


Eccentric Assembly with Additional top seal

The new top seal adds two additional layers of protection to help prevent bearing failure caused by harmful contaminants.




Additional Seal

Additional Seal



Ball Bearings



Ball Bearings

**Aluminum Driver Plate
with Through Hole**

**New Aluminum Driver Plate
without Through Hole**




The new solid bottom plate prevents contaminants from attacking the bottom of the bearing. Combined, these new features should prevent bearing failures!

Base Plate Assembly

EBG-20/C PIVOT BASE PLATE ASSEMBLY

SS 142015 PVT

SOLD INDIVIDUALLY




This kit contains everything needed to replace the eccentric assembly for the EBG-20/C. When replacing, Square Scrub[®] recommends installing new isolators as well. Included are: aluminum driver plate, 4 isolators, motor shaft spacer, motor shaft cap bolt, bearing bolts, eccentric assembly, crush washer, eccentric assembly key, grip face, anti-seize, & 100% silicone.

EBG-28 PIVOT BASE PLATE ASSEMBLY

SS 142815 PVT

SOLD INDIVIDUALLY




This kit contains everything needed to replace the eccentric assembly for the EBG-28. When replacing, Square Scrub[®] recommends installing new isolators as well. Included are: aluminum driver plate, 8 isolators, motor shaft spacer, motor shaft cap bolt, bearing bolts, eccentric assembly, crush washer, eccentric assembly key, grip face, anti-seize, & 100% silicone.



Watch the how-to
installation video

**Visit us online for full installation instructions
and detailed video tutorials.**

**squarescrub.com
800-557-6822**



HEPA & CRI Gold




HEPA Dry Vac Kit

SS EBG-HDVK - Sold Individually

The Square Scrub HEPA Dry Vac Kit attaches to all 20" & 28" Square Scrub machines. Since it only draws 4.5 amps, it can be plugged directly into the machine power with the included adapter. This vacuum can be converted to a backpack vac with optional accessories.






New & Improved!

Solution Tank

EBG-20/C - SS EBG-WTS20

EBG-28 - SS EBG-WTS28

The Square Scrub® Solution Tank attaches to all 20" and 28" Square Scrub Pivot machines. The new and improved Solution Tank includes a relocated water line that feeds into a front mounted dispersion bar. The release trigger is now located closer to the handle grips for optimal performance.



**Only compatible with Square Scrub Pivot machines.

***Specifications & information contained in this catalog are subject to changes without notice.



Go where the
big machines
can't.

Compact & Powerful



Weighing in at 21 lbs., the Doodle Scrub® EBG-9 gets in those tight spaces the big machines can't. Doodle Scrub deep cleans under urinals, behind toilets, and even works great on stairs. With a new patent pending handle/base design, the Doodle Scrub handle can be attached on either end or the middle of the base, allowing a more mop like motion for absolute versatility.

Scrub pads are available in SQP dry prep, tile and grout, xtreme sponge, and more.

The Doodle Scrub EBG-9 goes where you can't.

Versatility²

**Patent Pending

***Specifications & information contained in this catalog are subject to changes without notice.

Reaches Under Urinals



Works Great on VCT



Cleans Behind Toilets



Works Great on Stairs



800-557-6822
squarescrub.com

See the Doodle
Scrub in Action.



The innovative patent pending Doodle Scrub handle attaches to the base in TWO different ways giving the user maximum **Versatility²**

Clip the handle in the middle of the base,



Or end of the base to get in those tight spaces.



Look at how much dirt we pulled by only using water.

Before



After



Results shown from adding water, no chemicals needed.

Before




After



Obliterates nasty tile & grout buildup!

Before



After





**Patent Pending
***Specifications & information contained in this catalog are subject to changes without notice.




✓ Another
Tough Job Made
EASY!

Baseboard Scrubbing Attachment

Converts the Doodle Scrub® into the most highly effective
baseboard scrubbing machine available.



Before



See the
Doodle Skate® in action.



After






Baseboards



Durable nylon carry strap for easy transport.

Smooth pivoting action adjusts to wall contours.



Blue Tile & Grout pad works great on tile & grout, baseboards, stair risers & more.

Easy gliding non-marking wheels.



Full Pad Contact

Full pad contact for optimal cleaning.

4100 rpms of baseboard scrubbing action.



Innovators, Not Imitators

Doodle Skate turns the scrubbing action parallel to the baseboard.



See the
Doodle Skate®
in action.



Upright machine baseboard attachments simply hit against the baseboard.



One Package, All the Tools

Includes

**Doodle
SKATE**
BY SQUARE SCRUB



Includes

**Doodle
SCRUB**
BY SQUARE SCRUB

with Stainless Steel
Carry Strap & Handle Trigger



Also Includes

4 - Blue Pads

4 - White Driver Pads

2 - SHO Pads

4 - SQP Pads

1 - White Pad

2 - Tile & Grout Pads

1 - Xtreme Sponge



Floor Finish Application Tool




Available in 18" & 24"

18" - SS BOS18 | 24" - SS BOS24


Long lasting
American Made
Components



800-557-6822 | squarescrub.com



- Easy Release Handle



- No drip clamping mechanism
- Straight hose for easy cleaning



18" Replacement Microfiber Mophead
SS 0403Z



24" Replacement Microfiber Mophead
SS 0406Z

- Available in 18" and 24"
- Holds 5 quarts of finish
- No drip clamping mechanism
- Applies finish quickly and smoothly
- Easy to clean and maintain



18" T-bar Attachment - SS 0407Z
24" T-bar Attachment - SS 0411Z




18" T-bar Refill Pad - SS 0408Z
24" T-bar Refill Pad - SS 0412Z




3M TRIZACT™ TZ Diamond Abrasive Strips

Creates a smooth, highly refined surface.




Coarse

3M TRIZACT™
Diamond TZ Gold
TZD GOLD - Sold Individually



Medium

3M TRIZACT™
Diamond TZ Red
TZD RED - Sold Individually



Fine

3M TRIZACT™
Diamond TZ Blue
TZD BLUE - Sold Individually


Only 3 diamond steps!



One Size Fits All

Great for concrete, marble, terrazzo, & more.

Diamond Strips can be set in rows of 2 or 3.



Fewer diamonds used = Cost effective



More diamonds used = Time saved




The Doodle Scrub can be used to polish tighter spots & doorways.



3M Scotch-Brite™ Purple Diamond Floor Pad Plus


Diamond coated floor pads for cleaning & polishing



The dark purple bottom contains the diamond coated material.



Available for square & round machines



10.5" - P0511PD

20" - P1420PD

28" - P1428PD



19" - P0019PD

24" - P0024PD

27" - P0027PD

3M Scotchgard™ Stone Floor Protector

Hardener & protector for porous stone flooring



- Fast drying, & thin coating.
- Easy to apply with the Bucket on a Stick.
- Great for concrete, marble, terrazzo, & more.
- Lower maintenance than typical finishes.
- Reduces floor maintenance costs.



Watch the stone
polishing demo.





Blue Tile & Grout Pad

- Made of the same blue scrubbing material that has already proven to clean better with the Doodle Scrub.
- Integrated velcro backing extends the pad life and reduces slippage.



Inferior Green Material = Inferior Pad

- Longer and stiffer bristles scrub deeper, and outperform the traditional green tile & grout pads.
- The new Blue Tile & Grout Pad is nearly 1/2" thicker than the old green pad.
- More bristles per square inch. Cleans at least twice as good as the green pads.




Blue Tile & Grout Pad

10" SS P0511TGBV

The new Blue Tile & Grout pad is also available for the Doodle Scrub EBG-9.

Works great on those hard to reach grouted areas.

**Doodle
SCRUB**
BY SQUARE SCRUB





Available in 3 different sizes

Blue Tile & Grout Pad

20" SS P1420TGB

28" SS P1428TGB

The new Square Scrub Blue Tile & Grout Pad drastically outperforms the old style green pads. With longer bristles and more scrubbing material per square inch, the blue pad scrubs deeper and lasts longer than the traditional green pads.




800-557-6822
squarescrub.com

The SQP Pad dry preps up to 3,600 sq ft of finished VCT surface per hour.



SQP PAD

10.5"	P0511SQP	60/CASE
20"	P1420SQP	10/CASE
28"	P1428SQP	10/CASE



The SQP pad is a thin pad designed to remove several layers of acrylic finish in preparation for recoating. The SQP Pad is also great for prepping a gym floor for water based finish (verify with your gym finish vendor).
Use dry on VCT and Tile.



Use wet. The SHO Pad is only for the heaviest of chemical stripping jobs.

SHO PAD

10.5"	P0511SHO	20/CASE
20"	P1420SHO	5/CASE
28"	P1428SHO	5/CASE



The SHO Pad is extremely abrasive and heavy, with dense fibers. Best used when dirt and buildup are severe. Use wet on VCT and tile. Use with a white or blue driver to protect the grip face. Inspect driver every 15 minutes.

VCT Preparation Comparison - Total Labor Costs* Based on 1,000 sq ft of VCT Preparation

	Chemical Stripping: Rotary Machine	Dry Prep: Square Scrub
Hourly Rate**	\$14.00	\$14.00
Additional Payroll Cost***	\$4.20	\$4.20
Total Hourly Rate	\$18.20	\$18.20
Strip with 175 rpm 20” Rotary Machine requiring separate pick-up	75 min	N/A
Dry Prep with Square Scrub Machine	N/A	24 min
Pick-up with tank type wet vacuum and 16” orifice pick-up tool	23.40 min	N/A
Vacuum with 14” upright vacuum	N/A	21 min
Damp mop once with microfiber mop system	14.40 min	14.40 min
Apply one layer of floor finish using a mop in 36 minutes/layer	180 min (5 Layers)	N/A
Apply one layer of floor finish using the Bucket on a Stick in 24 min/layer	N/A	72 min (3 Layers)
Wait time between layers (1 Hour/Layer)	240 min (5 Layers)	120 min (3 Layers)
Total Labor	532.8 min/8.88 hours	251.4 min/4.19 hours
Total Labor Cost	\$161.61	\$76.26

*Based on ISSA Time Standards of 1000 sq ft of VCT Preparation.

**Information based on averages found at careerbliss.com - <http://www.careerbliss.com/jobs/floor-technician/salaries/>

***Based on 40% markup

Total Material Cost: Based on 1,000 sq ft of VCT Preparation

	Chemical Stripping: Rotary Machine	Dry Prep Square Scrub
Standard Chemical Stripper: (.5 Gallons, dilutes to 5.5 Gallons)* \$24/Bottle	\$96.00 (2 Gallons)	N/A
Standard Floor Finish: \$12.67/layer**	\$63.35 (5 Layers)	\$38.01 (3 Layers)
Black Rotary Chemical Stripping Pad	\$1.10***	N/A
SQP Pad	N/A	\$7.77****
Chemical Strip Shoes	\$10.00	N/A
Total Material Cost	\$170.45	\$45.78

*Based on product use recommendations of applying 5.5 gallons of diluted stripper to 250 sqft.

**Based on a one gallon price of a standard floor finish at \$19 and an average coverage rate of 1500 sqft per gallon and 1000 sqft being 66.66% of the average use.

***Information based on 25% pad consumption at the estimated price of \$4.37 per pad and an estimated pad use effectiveness of 4,000 sqft when accounting for use with chemicals and pad care/wear and tear.

****Based on estimated pad cost of \$11.65/pad and a maximum use of 1500 sqft (750 sqft/side) and 1000 sqft consuming 66.67% of the pad.

Overall Total Prep Costs: Based on 1000 sq ft of VCT Preparation

	Chemical Stripping: Rotary Machine	Dry Prep Square Scrub	Total Dry Prep Savings
Total Labor Cost	\$161.61	\$76.26	\$85.35
Total Material Cost	\$170.45	\$45.78	\$124.67
Overall Total Prep Cost	\$332.06	\$122.04	\$210.02

COST IS 64% LESS To Dry Prep & Recoat vs Chemical Stripping.

Estimated Water Savings: Based on 1000 sq ft of VCT Preparation

	Chemical Stripping: Rotary Machine	Dry Prep Square Scrub	Total Dry Prep Savings
Total Water - Stripping	approx. 20 gallons	N/A	20 gallons
Total Water - Rinsing (2x)	approx. 40 gallons	N/A vacuum & tack cloth	40 gallons
Total Water Used	approx. 60 gallons	0	60 gallons

Estimated 60 GALLONS OF WATER
saved with Dry Stripping Method (1000 sq ft).

*The Square Scrub® EBG-20/C
has earned the Carpet and Rug
Institute's Bronze Seal of
Approval for Superior Cleaning.*

SQUARE SCRUB

Versatility²



Microfiber Carpet Cleaning Pad

MICROFIBER CARPET CLEANING PAD—P1420CB

SOLD INDIVIDUALLY

Combined with Square Scrub Encapsulating Carpet Cleaner, the Microfiber Carpet Cleaning Pad deep cleans even the highest-traffic carpeting. Quicker drying time. Use wet on any carpeted surface.

**Durable!
Lasts up to 50
wash cycles.**



Encapsulating Carpet Cleaner

ENCAPSULATING CARPET CLEANER


**1 GAL BOTTLES
SOLD INDIVIDUALLY**

Designed for use with the Square Scrub Microfiber Carpet Cleaning Pad. Square Scrub Encapsulating Carpet Cleaner captures soil and dries to a non-sticky crystal that can be vacuumed up, and disposed of easily. Only 8 oz. required per gallon. A significant savings over other encapsulation cleaners. This product is Carpet and Rug Certified.



**800-557-6822
squarescrub.com**

***Specifications & information contained in this catalog are subject to changes without notice.

SANDSCREENS**10/CASE**

	14x20	14x28
60 Grit	S1420060	S1428060
80 Grit	S1420080	S1428080
100 Grit	S1420100	S1428100
120 Grit	S1420120	S1428120
150 Grit	S1420150	S1428150
180 Grit	N/A	S1428180

Sandcreens are ideal for finish removal, or repair of wood floor surfaces. Screens can be used to repair painted floor surfaces. Both sides of screens can be used.

Use with a thin white or Blue Driver Pad. Use wet or dry on wood or painted concrete.

Flat, Consistent, Even Screening

Productivity²®



Never underestimate the power of a straight line.

At Square Scrub, a straight line means efficiency. The ability to control your movement allows you to do more with one pass. Using an EBG machine helps you prep the work area faster and more efficiently, so you can move on to the next job.



**Screen Gym Floors up
to 10,000 sq ft/hr***



28 INCHES OF

SANDING AND

SCREENING POWER

***EBG-28 Machine results may vary.**

***Specifications & information contained in this catalog are subject to changes without notice.

PRO SANDPAPER

SOLD INDIVIDUALLY

Our Pro Sandpaper is double-sided & longer lasting than standard sandpaper, cutting paper usage drastically!

With grits ranging from the ultra-aggressive 16 to the popular 100 grit, these are great for smoothing wood surfaces. Both sides of this paper can be used. Use along with the White Driver Pad. Use dry on wood flooring or decks. Our 16 grit Pro Sandpaper works great dry for gum removal on concrete!



	14x20	14x28
16 Grit	PPSP1319016	PPSP1327016
24 Grit	PPSP1319024	PPSP1327024
36 Grit	PPSP1319036	PPSP1327036
60 Grit	PPSP1319060	PPSP1327060
80 Grit	PPSP1319080	PPSP1327080
100 Grit	PPSP1319100	PPSP1327100

Removes chair & drum sander marks



STANDARD SANDPAPER

20/CASE

Our Standard Sandpaper comes in a variety of grits to tackle any of your wood floor needs.

Use these for smoothing wood surfaces. Use along with the White Driver Pad.


Use dry on wood flooring or decks.

	14x20	14x28
20 Grit	SP1319020	SP1327020
36 Grit	SP1319036	SP1327036
60 Grit	SP1319060	SP1327060
80 Grit	SP1319080	SP1327080
100 Grit	SP1319100	SP1327100



Sands flat & even

Easy to Control



Abrader Plate - SAP

20" - P1319SAP

SOLD INDIVIDUALLY

This Carbide Tungsten steel abrader tool is designed for heavy duty use. The SAP (Square Abrader Plate) is perfect for linoleum removal, glue, or paint on concrete.

Only use the SAP with the Blue Driver Pad, and always use wet!

800-557-6822 | squarescrub.com



Hand scraping is going to take a while...

Driver & Cleaning Pads

Blue Driver



10.5" P0511BLU 18/Case
20" P1420BLU 5/Case
28" P1428BLU 5/Case

Ideal for use as a spacer between the machine & other pads, because of its superior ability to hold its form. It can also be used for heavier cleaning & buffing.

White Driver



10.5" P0511DRIVER 48/Case
20" P1420DRIVER 10/Case
28" P1428DRIVER 10/Case

1/4" thick pad used primarily as a spacer pad. Use this pad with sandpaper and diamonds. Always check spacer pad.
DO NOT USE WITH ABRADER PLATE!

Red Driver



20" P1420RED 5/Case
28" P1428RED 5/Case

Primarily used as a spacer pad between the machine and other pads. It's a light cleaning pad that can also be used for both heavy cleaning & buffing.

White Pad



10.5" P0511WHT 16/Case
20" P1420WHT 5/Case
28" P1428WHT 5/Case

The White Pad is used as a light duty polish pad. This thick pad is used without a driver pad, and is great for spreading chemicals while buffing.

SSE Pad



20" P1420SSE 5/Case
28" P1428SSE 5/Case

The SSE (Square Scrub Enhancer) Pad is a light duty restorative and polishing pad.

Xtreme Sponge



10.5" P0511XTR 5/Case
20" P1420XTR 5/Case
28" P1428XTR 5/Case

Use this pad to remove scuff marks on VCT or bathroom tile. A little water and this melamine pad deep cleans and restores shine between refinishing jobs. Use wet on VCT and tile.

Driver Pad Care = Longer Grip Face Life




Grip Face Care
Instructions

Checking driver pads regularly is key to a long lasting grip face. All driver pads wear out. The amount of time a driver pad will last varies greatly based on the task being done.

Proud to be American Made


Square Scrub machines are built in Jonesboro, AR.

Our machines are truly American Made. The steel used in our frame comes from Arkansas. The Leeson motor is made in Black River Falls, WI. We believe in American made products, and the opportunities created by supporting American companies. That is why we make every effort to incorporate components that are made right here in the United States of America.



Quality Control

Every machine we build is quality tested and inspected. We care about the reputation of American made products, so we strive to build a sturdy, hard-working, solid machine that is **BUILT TO LAST!**



Fast Delivery

Time is Money.

At Square Scrub, we know that your time is valuable. Our machines are designed to save you time, affording more money making opportunities. We know that you don't have time to wait weeks for your machine. That is why we strive to fulfill every machine order within one day of receiving an order. For pads and accessories, we do our best to get them out to you the next day, so you can get to work ASAP!



Connect With Us



800-557-6822 | squarescrub.com

Superior Cleaning Power



Doodle
mop
BY SQUARE SCRUB
EBG-16

UL/CSA/CE Certified	Yes
Total Assembled Weight	12 lbs
Maximum Weight Capacity	12 lbs
Powder Coated Steel Frame	10 gauge
3/4 " Solid Steel Axle	N/A
Handle Attachment Points	3
6"x2" Non-Marking Wheels	N/A
Motor	4100 rpm .33 hp
Operating Sound Output	50 db
Power Cord	30 ft/18 gauge
Lighted Plug	N/A
Amp Draw	1.2 amps
Pad Size	5.25x16
Number of Isolators	4
Oscillations	4100/minute
Removable Weights	N/A
Slotted Weights	N/A
Vibration Reducing Isolated Handle	N/A
Noise Reducing Weight Spacers	N/A
Stone Care Capable	N/A
Carpet & Rug Institute Certified	N/A
Dust Containment Kit	N/A
Built-in Hour Meter	N/A
Two-Piece Handle	N/A

Compact & Powerful



Doodle SCRUB
BY SQUARE SCRUB

EBG-9


UL/CSA/CE Certified	Yes
Total Assembled Weight	21 lbs
Maximum Weight Capacity	21 lbs
Powder Coated Steel Frame	10 gauge
3/4 " Solid Steel Axle	N/A
Handle Attachment Points	2
6"x2" Non-Marking Wheels	N/A
Motor	4100 rpm .33 hp
Operating Sound Output	59 db
Power Cord	30 ft/18 gauge
Lighted Plug	N/A
Amp Draw	1.2 amps
Pad Size	5.25x10.5
Number of Isolators	4
Oscillations	4100/minute
Removable Weights	N/A
Slotted Weights	N/A
Vibration Reducing Isolated Handle	N/A
Noise Reducing Weight Spacers	N/A
Stone Care Capable	Yes
Carpet & Rug Institute Certified	N/A
Dust Containment Kit	Optional
Built-in Hour Meter	N/A
Two-Piece Handle	N/A



800-557-6822
squarescrub.com

Patent Pending *Specifications & information contained in this catalog are subject to changes without notice.

EBG_{20/C}
BY SQUARE SCRUB




UL/CSA/CE Certified	Yes
Base Weight w/o Weights	106 lbs
Total Assembled Weight	156 lbs
Maximum Weight Capacity	232 lbs
Powder Coated Steel Frame	10 gauge
Stainless Steel Base	7 gauge
3/4 " Solid Steel Axle	Yes
Adjustable Handle	Yes
6"x2" Non-Marking Wheels	Yes
Motor	3450 1.5 hp
Operating Sound Output	69 db
Power Cord	50 ft/14 gauge
Lighted Plug	Yes
Amp Draw	7 amps
Pad Size	14x20
Number of Isolators	4
Oscillations	3450/minute
Removable Weights	Yes
Slotted Weights	Yes
Vibration Reducing Handle	Yes
Noise Reducing Weight Spacers	Yes
Stone Care Capable	Yes
Carpet & Rug Institute Certified	Yes
Dust Containment Kit	Yes
Built-in Hour Meter	Optional
Two-Piece Handle	Optional

*Machine shown with optional HEPA Vac Kit.



The EBG-20/C is the only orbital floor machine that is CRI Certified.



UL/CSA/CE Certified	Yes
Base Weight w/o Weights	117 lbs
Total Assembled Weight	197 lbs
Maximum Weight Capacity	197 lbs
Powder Coated Steel Frame	10 gauge
Stainless Steel Base	7 gauge
3/4 " Solid Steel Axle	Yes
Adjustable Handle	Yes
6"x2" Non-Marking Wheels	Yes
Motor	3450 1.5 hp
Operating Sound Output	69 db
Power Cord	50 ft/14 gauge
Lighted Plug	Yes
Amp Draw	9.6 amps
Pad Size	14x28
Number of Isolators	8
Oscillations	3450/minute
Removable Weights	Yes
Slotted Weights	Yes
Vibration Reducing Handle	Yes
Noise Reducing Weight Spacers	Yes
Stone Care Capable	No
Carpet & Rug Institute Certified	N/A
Dust Containment Kit	Yes
Built-in Hour Meter	Yes
Two-Piece Handle	Optional

800-557-6822
squarescrub.com

EBG-Series by Square Scrub®



SQUARE SCRUB
Versatility²
PIVOT



Doodle
MOP
BY SQUARE SCRUB


Doodle
SCRUB
BY SQUARE SCRUB




EBG-28



EBG-20/C



EBG-16



EBG-9

800-557-6822 | squarescrub.com

Floor Preparation Made Easy

Connect With Us



Share



Watch



Like



Tweet



Connect

SQUARE SCRUB
Versatility²

Square Scrub®
P.O. Box 1693
Jonesboro, AR 72403

